

NOTE TO REVIEWER: The following language is ADDED to the version of the NJTA 2004 Standard Supplementary Specifications which existed prior to the issuance of this DCA.

SECTION 201 - CLEARING AND GRUBBING

NOTE TO DESIGNER: Include in all Contracts involving tree clearing work.

201.03 METHODS OF CONSTRUCTION.

The following is added after the third paragraph:

Once a tree has been cut, it shall be removed from the Project Site within ten (10) working days.