

## New Jersey Turnpike Authority

PO Box 1121. New Brunswick. NJ 08903

## **Document Change Announcement**

2004 Standard Supplemental Specifications Removable Wet Weather Pavement Marking Tape

**DCA2007SS-08** 

**November 1, 2007** 

**Subject:** Revisions to Section 920 Traffic Control Devices, Subsection 920.10 Temporary

**Pavement Striping** 

These revisions pertain to the use of Removable Wet Weather Pavement Marking Tape on Authority Construction Contracts.

## **Instructions to Designers and Consultants**

Effective immediately, all contracts shall incorporate the revisions listed herein. For advertised contracts awaiting the opening of bids these revisions shall be incorporated via addendum. Contact your NJTA Project Manager for instruction. Attached revision is noted in *italics*.

Designers may access these revisions in the Standard Supplemental Specification, which is available on the following Authority Web Page: http://www.state.nj.us/turnpike/nj-buss.htm

## **Information for In-House Staff**

The product described in this specification has an operational temperature limit of 50 degrees for installation and 40 degrees for removal. If this specification is being used on a project in early spring/late fall, it is necessary to confirm from the Operations Department that daytime closings are allowable for tape placement or removal.

The specification revisions have been incorporated into the Standard Supplemental Specification, which is available in the S: / drive. Please distribute the information to your Project Managers and have them direct their consultants appropriately.

Recommended By:	Approved By:
J. Lawrence Williams, P.E.	Richard J. Raczynski, P.E.
Assistant Chief Engineer, Construction	Chief Engineer

Distribution: Senior Staff Engineering, Operations, Law & Maintenance Depts., UTCA, AGC, All Prequalified Consultant Firms, File