

New Jersey Turnpike Authority

P.O. Box 5042, Woodbridge, NJ 07095



August 27, 2024

Document Change Announcement

2016 Standard Supplementary Specifications

Inlet or Manhole Casting

DCA2024SS-07

Subject: Revisions to

Section 503 Manholes and Inlets, Subsection 503.03 Methods of Construction

Description of Change:

This DCA clarifies that inlets or manholes requiring more than 1 foot of repair shall be reconstructed in accordance with Subparagraph 503.03(H)(2).

Notice to New Jersey Turnpike Authority Staff and Design Consultants

Effective immediately, all contracts currently in the design phase shall incorporate the revisions herein. For advertised contracts awaiting the opening of bids this revision shall be incorporated via addendum. Contact your New Jersey Turnpike Authority Project Manager for instruction.

The revisions may be accessed on the Authority's webpage: <https://www.njta.com/doing-business/professional-services>

Recommended By:

(signature on original)

Lamis T. Malak, P.E.
Deputy Chief Engineer - Design

Approved By:

(signature on original)

Daniel L. Hesslein, P.E.
Acting Chief Engineer

Distribution: Senior Staff Engineering, Law, Maintenance & Operations Depts., All Prequalified Consultant Firms, File

NOTE: All text herein is ADDED to the latest version of the 2016 Standard Supplementary Specifications.

503.03 Methods of Construction


(H) Reconstruction and Conversion of Existing Structures

Add the following to the end of Subparagraph (5):

Repair of inlets and manholes in excess of 1 foot shall be considered reconstructing manholes and inlets.

New Jersey Department of Transportation

1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



Baseline Document Change Announcement

ANNOUNCEMENT: BDC24S-01

DATE: March 27, 2024

SUBJECT: Modifying an Inlet or Manhole
- Revision to Subpart 602.03.03 of the 2019 Standard Specifications for Road and Bridge Construction.

Subpart 602.03.03 of the Standard Inputs and the 2019 Standard Specifications for Road and Bridge Construction has been revised to clarify the requirements and therefore to prevent misunderstanding and claims from the contractors.

The following revisions have been incorporated into the 2019 Standard Specifications via 2019 Standard Inputs, SI2019:

602.03.03 Set Casting, Reset Casting, and Reconstructed Inlet and Manhole
THE FIRST PARAGRAPH IS CHANGED TO:


When modifying less than 1 foot of an inlet or manhole, set a new casting, or reset the existing casting. When modifying 1 foot or more of an inlet or manhole, reconstruct the inlet or manhole.

Implementation Code R (ROUTINE)


Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

Recommended By:

Approved By:



Tina M. Shutz
Acting Director
Capital Program Support



Parth Oza, P.E.
Assistant Commissioner
Capital Program Management
and Deputy State Transportation Engineer