

New Jersey Turnpike Authority

P.O. Box 5042, Woodbridge, NJ 07095



December 31, 2024

Document Change Announcement

***2016 Standard Supplementary Specifications
Prefabricated Modular Wall Height
DCA2024SS-09***

Subject: Revisions to

Section 427 Prefabricated Modular (PM) Walls, Subsection 427.02 Materials

Description of Change:

This DCA revises the prefabricated modular wall height limitation and makes other minor changes.

Notice to New Jersey Turnpike Authority Staff and Design Consultants

Effective immediately, all contracts currently in the design phase shall incorporate the revisions herein. For advertised contracts awaiting the opening of bids this revision shall be incorporated via addendum. Contact your New Jersey Turnpike Authority Project Manager for instruction.

The revisions may be accessed on the Authority's webpage: <https://www.njta.com/doing-business/professional-services>

Recommended By:

(signature on original)

Lamis T. Malak, P.E.
Deputy Chief Engineer - Design

Approved By:

(signature on original)

Daniel L. Hesslein, P.E.
Chief Engineer

Distribution: Senior Staff Engineering, Law, Maintenance & Operations Depts., All Prequalified Consultant Firms, File

NOTE: All text herein is ADDED to the latest version of the 2016 Standard Supplementary Specifications.

SECTION 427 – PREFABRICATED MODULAR (PM) WALLS

427.02 Materials

(A) PREFABRICATED MODULAR WALL SYSTEMS.

Delete the entire Paragraph and replace with the following:

The Contractor shall make their own arrangements to purchase the materials and services from one of the Authority's approved Wall Manufacturers. Selection of only one (1) PM Wall System and no more than one (1) Wall Manufacturer will be permitted for use on the Contract.

An on-site technical representative from the selected Wall Manufacturer shall be present to assist and instruct during the installation of the first two-module courses of the first wall in the Contract, as a minimum.